

UTAH OIL AND GAS CONSERVATION COMMISSION

REMARKS: WELL LOG _____ ELECTRIC LOGS _____ FILE X WATER SANDS _____ LOCATION INSPEC _____ SUB. REPORT/abd. _____

960410 Oper. Nm. Chg. 970514 Location abandoned eff. 4/30/97:

DATE FILED DECEMBER 20, 1994

LAND: FEE & PATENTED

STATE LEASE NO.

PUBLIC LEASE NO.

U-096547

INDIAN

DRILLING APPROVED: MARCH 7, 1995

SPUDED IN:

COMPLETED:

PUT TO PRODUCING:

INITIAL PRODUCTION:

GRAVITY A.P.I.

GOR:

PRODUCING ZONES:

TOTAL DEPTH:

WELL ELEVATION:

DATE ABANDONED:

April 30, 1997 LA'D

FIELD:

MONUMENT BUTTE FIELD

UNIT:

JONAH UNIT

COUNTY:

DUCHESE

WELL NO.

MONUMENT BUTTE FEDERAL #22-14J

API NO. 43-013-31489

LOCATION

2134' FNL FT. FROM (N) (S) LINE,

2198' FWL

FT. FROM (E) (W) LINE.

SE NW

1/4 - 1/4 SEC.

14

TWP.

RGE.

SEC.

OPERATOR

TWP.

RGE.

SEC.

OPERATOR

9S

16E

14

EQUIT RES ENERGY CO



**EQUITABLE RESOURCES
ENERGY COMPANY**

BALCRON OIL DIVISION

1601 Lewis Avenue
P.O. Box 21017
Billings, MT 59104

Office: (406) 259-7860
FAX: (406) 245-1365 ☐
FAX: (406) 245-1361 ☒

December 19, 1994

-- VIA FEDERAL EXPRESS --

Bureau of Land Management
170 South 500 East
Vernal, UT 84078

Gentlemen:

Enclosed are Applications for Permit to Drill the wells on the enclosed list.

As operator, we hereby request that the status of this well be held tight for the maximum period allowed by Federal and State regulations.

Archeology and palentology surveys have been ordered and reports will be sent to you as soon as they are complete.

Sincerely,


Bobbie Schuman

Bobbie Schuman
Regulatory and Environmental Specialist

/hs

Enclosures

cc: Utah Division of Oil, Gas and Mining



STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL**APPLICATION FOR PERMIT TO DRILL OR DEEPEN**


1A. Type of Work: DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/>		5. Lease Designation and Serial Number: Federal #U-096547
B. Type of Well: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER: SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		6. If Indian, Allottee or Tribe Name: n/a
2. Name of Operator: Equitable Resources Energy Company, Balcron Oil Division		7. Unit Agreement Name: Jonah Unit
3. Address and Telephone Number: P.O. Box 21017; Billings, MT 59104 (406) 259-7860		8. Farm or Lease Name: Balcron Monument Federal
4. Location of Well (Footages) At Surface: SE NW Setion 14, T9S, R15E 2134' FNL, 2198' FWL At Proposed Producing Zone:		9. Well Number: #22-14J
14. Distance in miles and direction from nearest town or post office: Approximately 13 miles southwest of Myton, Utah		10. Field and Pool, or Wildcat: Monument Butte/Green River
15. Distance to nearest property or lease line (feet):		11. Qtr/Qtr, Section, Township, Range, Meridian: SE NW 14, T9S, R16E
16. Number of acres in lease:		12. County: Duchesne
17. Number of acres assigned to this well:		13. State: UTAH
18. Distance to nearest well, drilling, completed, or applied for, on this lease (feet):		20. Rotary or cable tools: Rotary
19. Proposed Depth: 5,600'		22. Approximate date work will start: 3/1/95
21. Elevations (show whether DF, RT, GR, etc.): GL 5594.3'		

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
See EXHIBIT	"D" Drilling Program/Casing Design			

DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

Operator intends to drill this well in accordance with the attached Federal Application for Permit to Drill.



24. Name & Signature: <u>Bobbie Schuman</u> Bobbie Schuman	Regulatory and Environmental Specialist Title: <u>Environmental Specialist</u> Date: <u>12-19-94</u>
APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING DATE: <u>12/19/94</u> BY: <u>[Signature]</u> WELL SPACING: <u>9.5</u>	
API Number Assigned: <u>43-013-31489</u>	Approval: <u>[Signature]</u>

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL


APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. U-096547
b. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/> SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME n/a
2. NAME OF OPERATOR Equitable Resources Energy Company, Balcron Oil Division		7. UNIT AGREEMENT NAME Jonah Unit
3. ADDRESS OF OPERATOR P.O. Box 21017; Billings, MT 59104		8. FARM OR LEASE NAME Balcron Monument Federal
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)* At surface SE NW Section 14, T9S, R16E 2134' FNL, 2198' FWL		9. WELL NO. #22-14J
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* Approximately 13 miles southwest of Myton, Utah		10. FIELD AND POOL, OR WILDCAT Monument Butte/Green River
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any)		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 14, T9S, R16E
16. NO. OF ACRES IN LEASE		12. COUNTY OR PARISH Duchesne
17. NO. OF ACRES ASSIGNED TO THIS WELL		13. STATE UTAH
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.		20. ROTARY OR CABLE TOOLS Rotary
19. PROPOSED DEPTH 5,600'		22. APPROX. DATE WORK WILL START* 3/1/95
21. ELEVATIONS (Show whether DF, RT, GR, etc.) GL 5594.3'		

23. PROPOSED CASING AND CEMENTING PROGRAM				
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
See EXHIBIT "D" Drilling Program/Casing Design				

Operator intends to drill this well in accordance with the attached permit. A listing of EXHIBITS is also attached.

SELF CERTIFICATION: I hereby certify that I am authorized, by proper lease interest owner, to conduct these operations associated with the application. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Equitable Resources Energy Company as principal and Safeco Insurance Company of America as surety under BLM Bond No. MT 0576 (Nationwide Oil & Gas Bond #5547188) who will be responsible for compliance with all of the terms and conditions of that portion of the lease associated with this application.



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and depths. Give blowout preventer program, if any.


24. SIGNED <u>Bobbie Schuman</u>		Regulatory and Environmental Specialist		DATE <u>12-19-94</u>
(This space for Federal or State office use)				
PERMIT NO. <u>43-013-31489</u>	APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING			
APPROVED BY <u>M. Matthews</u>	DATE: <u>3/7/95</u>			
CONDITIONS OF APPROVAL, IF ANY	BY: <u>P. Trokum</u>			

*See Instructions On Reverse Side

T9S, R16E, S.L.B.&M.

S89°59'W (G.L.O.) Basis of Bearings
2625.36' - Measured

N89°59'32"W - 2632.00' (Meas.)



S89°54'W - 79.82 (G.L.O.)



= SECTION CORNERS LOCATED

BASIS OF BEARINGS; G.L.O. DATED 1910


BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SE)

EQUITABLE RESOURCES ENERGY CO.

WELL LOCATION, BALCRON MONUMENT FEDERAL #22-14J, LOCATED AS SHOWN IN THE SE 1/4 NW 1/4 OF SECTION 14, T9S, R16E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM THE ORIGINALS OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



TRI STATE LAND SURVEYING & CONSULTING
38 EAST 100 NORTH, VERNAL, UTAH 84078
(801) 781-2501

SCALE: 1" = 1000'	SURVEYED BY: G.S. S.S.
DATE: 11-4-94	WEATHER: COOL
NOTES:	FILE #22-14J

EXHIBIT "K"

Balcron Monument Federal #41-12J
NE NE Section 12, T9S, R16E
Duchesne County, Utah
395' FNL, 476' FEL
Field: Monument Butte (Jonah Unit)
FLS #U-44426
PTD: 5,750' (Green River formation)
GL: 5457.6'

Balcron Monument Federal #42-12J
SE NE Section 12, T9S, R16E
Duchesne County, Utah
2550' FNL, 391' FEL
Field: Monument Butte (Jonah Unit)
FLS #U-035521
PTD: 5,700' (Green River formation)
GL: 5474.4'

Balcron Monument Federal #12-14J
SW NW Section 14, T9S, R16E
Duchesne County, Utah
2004' FNL, 658' FWL
Field: Monument Butte (Jonah Unit)
FLS #U-096547
PTD: 5,600' (Green River formation)
GL: 5605.2'

Balcron Monument Federal #22-14J
SE NW Section 14, T9S, R16E
Duchesne County, Utah
2134' FNL, 2198' FWL
Field: Monument Butte (Jonah Unit)
FLS #U-096547
PTD: 5,600' (Green River formation)
GL: 5594.3'

Balcron Monument Federal #32-14J
SW NE Section 14, T9S, R16E
Duchesne County, Utah
1980' FNL, 1980' FEL
Field: Monument Butte (Jonah Unit)
FLS #U-096547
PTD: 5,600' (Green River formation)
GL: 5572'

Balcron Monument Federal #42-14J
SE NE Section 14, T9S, R16E
Duchesne County, Utah
1882' FNL, 773' FEL
Field: Monument Butte (Jonah Unit)
FLS #U-096550
PTD: 5,650' (Green River formation)
GL: 5604.9'

Balcron Monument Federal #11-7J

NW NW Section 7, T9S, R17E

Duchesne County, Utah

681' FNL, 447' FWL

Field: Monument Butte (Jonah Unit)

FLS #U-44426

PTD: 5,700' (Green River formation)

GL: 5343.2'

Balcron Monument Federal #12-7J

SW NW Section 7, T9S, R17E

Duchesne County, Utah

1965' FNL, 620' FWL

Field: Monument Butte (Jonah Unit)

FLS #U-44426

PTD: 5,600' (Green River formation)

GL: 5338.2'

NOTE: This location has already been built. It was formerly the Alta #7E location, built but not drilled.

EXHIBITS

- A PROPOSED DRILLING PROGRAM
- B PROPOSED SURFACE USE PROGRAM
- C GEOLOGIC PROGNOSIS
- D DRILLING PROGRAM/CASING DESIGN/WELLBORE DIAGRAM
- E HAZMAT DECLARATION
- F EXISTING & PLANNED ACCESS ROADS (MAPS A & B)
- G WELLSITE LAYOUT
- H BOPE SCHEMATIC
- I EXISTING ROADS (MAP C)
- J PROPOSED PRODUCTION FACILITY DIAGRAM
- K SURVEY PLAT
- L LAYOUT/CUT & FILL DIAGRAM

11/2/94

CONFIDENTIAL

AS OPERATOR, WE HEREBY REQUEST THAT THE STATUS OF THIS WELL BE HELD TIGHT FOR THE MAXIMUM PERIOD ALLOWED BY FEDERAL AND STATE REGULATIONS.

Equitable Resources Energy Company
Balcron Oil Division
P.O. Box 21017
Billings, MT 59104
(406) 259-7860

EQUITABLE RESOURCES ENERGY COMPANY
Balcron Oil Division
Jonah Unit
Balcron Monument Federal #22-14J
SE NW Section 14, T9S, R16E
Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162-3.1 (d):

1. ESTIMATED IMPORTANT GEOLOGICAL MARKERS:

See Geologic Prognosis (EXHIBIT "C")

2. ESTIMATED DEPTHS OF ANTICIPATED OIL, GAS OR WATER:

See Geologic Prognosis (EXHIBIT "C")

3. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

- a. EXHIBIT "H" is a schematic of the BOP equipment and choke manifold. A 2M system will be used. The BOPE will be installed after setting 8-5/8" casing at 260'. The blind rams and pipe rams will be tested to 1500 psi. Pipe rams will be operationally checked each 24-hour period and blind rams each time pipe is pulled out of the hole.
- b. The BOPE will be tested to 1500 psi when initially installed, whenever any seal subject to test pressure is broken, and following related repairs. The pipe and blind rams will be activated at least weekly and on every trip the pipe and blind rams will be activated.
- c. An accumulator of sufficient capacity to open the hydraulically-controlled choke valve lines (if so equipped), close all rams, and retain a minimum of 200 psi above precharge on the closing manifold without the use of the closing unit pumps will be installed during the drilling of this well.
- d. An upper kelly cock will be used during the drilling of this well.
- e. Visual mud monitoring equipment will be used to detect volume changes indicating loss or gain in circulating fluid volume.
- f. Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control.

4. PROPOSED CASING AND CEMENTING PROGRAM:

- a. Surface casing will be set in the Uinta formation to approximately 260' and cemented to surface.
- b. All potentially productive hydrocarbon zones will be isolated.

- c. Casing designs are based on factors of burst: 1.25, collapse: 1.125, and joint strength: 1.8.
- d. All casing strings will be pressure tested to 0.22 psi/ft. of casing string length or 1500 psi whichever is greater (not to exceed 70% of yield).
- E. For details of casing, cement program, drilling fluid program, and proposed mud program, see the following attachment:

Drilling Program/Casing Design (EXHIBIT "D")

5. HAZARDOUS PRESSURES, TEMPERATURES, FLUIDS/GASSES EXPECTED:

- a. Expected bottom hole temperature is 125 degrees F. Expected bottom hole pressure is 1500 psi.
- b. No abnormal pressures or temperatures have been noted or reported in wells drilled to the Green River formation in this area.
- c. No dangerous levels of hydrogen sulfide, hazardous fluids, or gasses have been found, reported, or known to exist at the depth to be drilled in this well, in this area.

6. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

- a. The drilling operations for this well will begin as soon after APD approval as possible.
- b. These drilling operations should be completed within 12 days after spudding the well depending on weather and hole conditions.
- c. If the well is productive, a sundry notice and plat showing exact installed facilities will be submitted.
- d. If this well is non-productive, a sundry notice will be filed with the BLM District Office within 30 days following completion of the well for abandonment.

7. OTHER

- a. Operator requests a variance to regulations requiring a straight run blooie line.
- b. Operator requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line.

SURFACE USE PROGRAM

EQUITABLE RESOURCES ENERGY COMPANY
Balcron Oil Division
Jonah Unit
Balcron Monument Federal #22-14J
SE NW Section 14, T9S, R16E
Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162.3-1 (d):

1. **EXISTING ROADS:**

- a. From Myton, Utah, take Highway #40 west out of town 1.6 miles to the Sand Wash road. Go south on the Sand Wash road for approximately 9.8 miles to an intersection with the Monument Butte Gas Plant/Jonah Unit road. Turn right and continue 5.4 miles to road intersection. Turn left and proceed 1.5 miles to proposed access road sign. Follow flags 0.4 mile to location.
- b. Existing roadways need no improvements for these drilling operations.
- c. All existing roads used by these drilling operations will be maintained in the same or better condition as were existing prior to entry.
- d. See EXHIBIT "F" Maps A and B for access route.

2. **PLANNED ACCESS ROADS:** See EXHIBIT "F" Maps A & B

- a. Length: Approximately 0.4 miles of new access road will be required.
- b. Width: Maximum 30' overall right-of-way with an 18' running surface.
- c. Maximum grade: < 8%
- d. Turnouts: None
- e. Drainage design: Low water crossing if necessary.
- f. No culverts or bridges are necessary.
- g. Surface materials: Any surface materials which are required will be native materials from the location and/or access site.
- h. No gates, cattleguards, or fence cuts and/or modifications to existing facilities will be required.

- i. All travel will be confined to location and access routes.
- j. All access roads and surface disturbing activities will conform to the standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. This shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed safe road. If necessary prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Road drainage crossings will be of the typical dry creek draining crossing type. Crossings, if necessary, will be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading will not be done during muddy conditions. Should mud holes develop, they will be filled in and detours around them will be avoided.

- k. If a right-of-way is needed for access, please consider this Application for Permit to Drill as the application for right-of-way.

3. LOCATION OF EXISTING WELLS:

See EXHIBIT "I" Map C.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

- a. Upon completion, a sundry notice and plat showing exact production facilities will be submitted.
- b. All above-ground facilities will be painted earthtone color Desert Brown #10Y/R in accordance with the Munsell Soil Color chart within six months of the well completion unless prior written approval to proceed with another alternative has been granted via Sundry Notice.
- c. See EXHIBIT "J" for the Proposed Production Facility Diagram.

5. LOCATION AND TYPE OF WATER SUPPLY:

- a. The drilling water source will be obtained from a private source owned by Joe Shields.
- b. The drilling water will be hauled by truck to the location site.

6. CONSTRUCTION ROAD/LOCATION MATERIALS:

- a. Any construction materials which are required will be native materials from the location and/or access site.
- b. All construction materials for this location site and access road shall be borrowed material accumulated during the construction of the site and road. No additional construction material from other sources is anticipated at this time. If additional construction material is needed, it will be from an approved source.
- c. Reasonable precautions will be taken to protect all lands.

7. METHODS FOR HANDLING WASTE MATERIALS AND DISPOSAL:

- a. Garbage will be stored in a dumpster and disposed of according to local and state regulations, at an approved facility. Disposal will not be allowed on location. No trash will be disposed of in the reserve pit.
- b. Fluids produced during the completion operation will be collected in test tanks. Any spills of oil, gas, salt water or other noxious fluids will be cleaned up and hauled to an approved disposal site. Burning will not be allowed.
- c. The reserve pit will be lined. If a plastic nylon reinforced liner is used, it will be torn and perforated before backfilling of the reserve pit.
- d. Saltwater or testing tanks will be located and/or diked so that any spilled fluids will flow into the reserve pit. Saltwater tanks will not be placed on topsoil stockpiles.
- e. Any produced water will be contained on site for a period not to exceed 90 days.
- f. Sewage will be disposed of according to county and state requirements. Sealed chemical portable toilets will be on location during these drilling operations. Waste and chemicals will not be disposed of on location.
- g. Cuttings will be deposited in the reserve pit.

8. ANCILLARY FACILITIES:

None anticipated.

9. LOCATION SITE LAYOUT:

- a. The proposed location site and elevation plat is shown on EXHIBIT "K".

- b. The drill pad layout, showing elevations, orientation, and access to the pad is shown on EXHIBIT "L".
- c. The drilling rig facilities layout is shown on EXHIBIT "G". No permanent living facilities are planned. There will be two or three trailers on location during drilling operations.
- d. The reserve pit and the blooie pit will be constructed as a combination pit capable of holding 12,000 bbls of fluid. The size of the pit will be approximately equivalent to four times the TD hole volume. The blooie pit might be used for testing, but only after the drilling is completed and the drilling equipment and personnel are off the location.
- e. The reserve pit will be located on the West side of the location.
- f. If needed, flare pit will be located downwind of the prevailing wind directions a minimum of 100' from the wellhead and 30' from the reserve pit fence.
- g. Stockpiled topsoil (first 6 inches) will be stored on the East side between corners 1 and 2.
- h. Access to the wellpad will be from the East near corner 8.
- i. All pits will be fenced according to the following minimum standards:
 - a. 39-inch net wire will be used with at least one strand of barbed wire on top of the net wire unless pipe or some type of reinforcement rod is attached to the top of the entire fence.
 - b. The net wire shall be no more than 2 inches above the ground. If barbed wire it shall be 3 inches above the net wire. Total height of fence will be at least 42 inches.
 - c. Corner posts will be cemented and/or braced in such a manner to keep the fence tight at all times. Standard steel, wood, or pipe posts will be used between the cornerbraces. Maximum distance between any two posts will be no greater than 16'.
 - d. All wire will be stretched before it is attached to the corner posts.

The reserve pit will be fenced on three sides during drilling operations and on the fourth side when the rig moves off locations. Pits will be fenced and maintained until clean-up.

10. PLANS FOR RECLAMATION OF LOCATION SITE:

The BLM will be contacted prior to commencement of any reclamation operations.

Producing location:

- a. Immediately upon well completion, the location and surrounding areas will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.
- b. Immediately upon well completion, any hydrocarbons in the pit will be removed in accordance with 43 CFR 3162.7-1.
- c. If a plastic nylon reinforced liner is used, it will be torn and perforated before backfilling of the reserve pit.
- d. The reserve pit and that portion of the location not needed for production facilities or operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 120 days from the date of well completion. Before any dirt work takes place, the reserve pit will have all fluids and hydrocarbons removed and all trash will be removed.

Dry hole/abandoned location:

At such time as the well is plugged and abandoned, operator will submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP:

Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

12. OTHER INFORMATION:

- a. An Archeology Survey will be provided as soon as it is completed.
- b. If unexpected cultural resources are observed during construction or reclamation operations, Equitable Resources Energy Company's Balcron Oil division will suspend operations in the vicinity of the discovery and immediately report the finding to the BLM District Office.
- c. Operator will have on site a copy of the Surface Use Program and a copy of the supplemental conditions.
- d. Drilling operations will be conducted in accordance with the Bureau of Land Management conditions of approval when received.

- e. If needed, instructions regarding a silt catchment dam being constructed will be provided for in the Conditions of Approval.

13. OPERATOR'S REPRESENTATIVES:

Equitable Resources Energy Company, Balcron Oil Division
1601 Lewis Avenue
P.O. Box 21017
Billings, Montana 59104
(8:00 a.m. to 5:00 p.m.)
(406) 259-7860
FAX: (406) 245-1361

Dave McCoskery, Operations Manager Home: (406) 248-3864
Mobile: (406) 698-3732

Dale Griffin, Operations Supervisor Mobile: (801) 828-7291
Home: (801) 781-1018

14. CERTIFICATION:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that any statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Equitable Resources Energy Company's Balcron Oil Division and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

December 19, 1994
Date

Bobbie Schuman
Bobbie Schuman
Regulatory and Environmental
Specialist
Equitable Resources Energy
Company, Balcron Oil Division

/rs

Galcron Oil Well Prognosis

EXHIBIT "C"

Well Name	BALCRON MONUMENT FEDERAL #22-14J		Exploratory		Control Well	BMF #21-14J
Location	SE NW SECTION 14-T9S-R16E, 2134' FNL, 2198' FWL		Development	X	Operator	EREC
County	DUCHESNE		Field	JONAH UNIT	KB	5602
State	UTAH		Section	SE NW 14	Section	NE NW 14
Total Depth	5600		Township	9S	Township	9S
GL (Ung)	5594.3	EST. KB 5603	Range	16E	Range	16E

[illegible]

Samples

50' FROM 1400' TO 3800'

30' FROM 3800' TO TD

5' THROUGH EXPECTED PAYS

5' THROUGH DRILLING BREAKS

DST,s

DST #1 NONE

DST #2

DST #3

DST #4

Wellsite Geologist

Name:

From: _____ to: _____

Address:

Phone #

Fax #

Logs

DLL FROM SURF CSG TO TD

LDT/CNL FROM 3500' TO TD

Cores

Core #1 NONE

Core #2

Core #3

Core #4

Mud Logger/Hot Wire

Company:

Required: (Yes/No) YES

Type: TWO MAN

Logger:

Phone #

Fax #

Comments:

Report To: 1st Name: DAVE BICKERSTAFF

2nd Name: KEVEN REINSCHMIDT

Prepared By: K.K. REINSCHMIDT

12/13/94

Phone # (406)259-7860

Phone # "

Phone #

wk. 245-2261

wk. 248-7026

wk.

Equitable Resources Energy Company
Balcron Oil Division

EXHIBIT "D"
Page 1 of 2

DRILLING PROGRAM

WELL NAME: Balcron Monument Fed. 22-14J PROSPECT/FIELD: Jonah Unit
LOCATION: SE NW Sec.14 Twn.9S Rge.16E
COUNTY: Duchesne STATE: Utah

TOTAL DEPTH: 5600

HOLE SIZE INTERVAL

12 1/4" 0 to 260'
7 7/8" 260 to T.D.

CASING	INTERVAL		CASING		
STRING TYPE	FROM	TO	SIZE	WEIGHT	GRADE
Surface Casing	0	260	8 5/8"	24 #/Ft	J-55
Production Casing	0	T.D.	5 1/2"	15.50#/Ft	K-55
(All Casing will be new, ST&C)					

CEMENT PROGRAM

Surface 150 sacks 75% Class "G" 25% Poz with 2% CaCl and 1/4 #/Sk Flocele.
(Cement will be circulated to surface.)

Production 180 sacks Western Super G consisting of 47 #/sk G, 20 #/sk Poz A, 17 #/sk CSE, 3% salt, 2% gel, and 2 #/sk Hi-Seal. (Yield=2.76 Cu.Ft./Sk Weight=11.08 PPG) Tailed with 300 sacks 50-50 Poz with 2% gel, 1/4 #/sk Cello-seal and 2 #/sk Hi-seal. Yield=1.24 Cu.Ft./Sk Weight=14.30 PPG)
a.) Actual cement volume will be determined from caliper log.
b.) Actual cement top will be specified in conditions of approval.

PRELIMINARY
DRILLING FLUID PROGRAM

TYPE	FROM	TO	WEIGHT	PLAS. VIS	YIELD POINT
Air and air mist	0	260	N.A.	N.A.	N.A.
Air/Air Mist/KCl Water	260	T.D.	8.7-8.9	N.A.	N.A.

Depending on the drilling contractor either:

- Drilling will be with air and air mist from surface to as deep as hole conditions allow. 2% KCl fluid will be used for the remainder of the hole.
- Drilling will be done using 2% KCl water and gel.

COMMENTS

- No cores or DST's are planned.

DMM/12/16/94

BALCRON OIL CO.

Operator: BALCRON OIL	Well Name: Monument Fed.22-14J
Project ID:	Location: Duchesne/Utah

Design Parameters:

Mud weight (8.80 ppg) : 0.457 psi/ft
 Shut in surface pressure : 2000 psi
 Internal gradient (burst) : 0.100 psi/ft
 Annular gradient (burst) : 0.000 psi/ft
 Tensile load is determined using air weight
 Service rating is "Sweet"

Design Factors:

Collapse : 1.125
 Burst : 1.00
 8 Round : 1.80 (J)
 Buttress : 1.60 (J)
 Body Yield : 1.50 (B)
 Overpull : 0 lbs.

Length (feet)		Size (in.)	Weight (lb/ft)	Grade	Joint	Depth (feet)	Drift (in.)	Cost
1	5,600	5-1/2"	15.50	K-55	ST&C	5,600	4.825	
	Collapse Load Strgth S.F. (psi) (psi)			Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Tension Load Strgth S.F. (kips) (kips)	
1	2560	4040	1.578	2560	4810	1.88	86.80	222 2.56 J

Prepared by : McCoskery, Billings, MT

Date : 12-16-1994

Remarks :

Minimum segment length for the 5,600 foot well is 1,500 feet.

The mud gradient and bottom hole pressures (for burst) are 0.457 psi/ft and 2,560 psi, respectively.

NOTE: The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser. Costs for this design are based on a 1990 pricing model. (Version 1.0G)

EXHIBIT E


- A. Hazardous chemicals 10,000 pounds of which will most likely be used, produced, stored, transported, or disposed of in association with the proposed action of drilling, completing and producing this well:

We anticipate that none of the hazardous chemicals in quantities of 10,000 pounds or more will be associated with these operations.

- B. Extremely hazardous substances threshold quantities (per Howard Cleavinger 11/30/93) of which will be used, produced, stored, transported, or disposed of in association with the proposed action of drilling, completing and producing this well:


We anticipate that none of the extremely hazardous substances in threshold quantities per 40 CFR 355 will be associated with these operations.

12/1/93
Revised 12/7/93
/rs



EQUITABLE RESOURCES CO.


BALCRON MONUMENT FEDERAL #22-14J
SECTION 14, T9S, R16E, S.L.B.&M.
TOPO "B"



SCALE: 1" = 2000'

Tri State
Land Surveying, Inc.
(801) 781-2501
38 WEST 100 NORTH VERNAL, UTAH 84078

EQUITABLE RESOURCES ENERGY CO. WELLSITE LAYOUT



TRI-STATE
LAND SURVEYING, INC.
38 WEST 100 NORTH, VERMILION, UTAH 84078
801-781-2501

UNION DRILLING RIG #17

Hex Kelly -

Rotating Head

Adj. Choke

Air Bowl

7" Flowline

#3000
Blind Rim - Pipe Rim


3" Gate Valve

3" Gate Valve

3" Choke Line

Adj. Choke


#3000 Stack








38 WEST 100 NORTH VERNAL, UTAH 84078

EXHIBIT "J"

Balcron Monument Federal 22-14J
SE NW Sec. 14, T9S, R16E
Duchesne County, Utah
Federal Lease #U-096547
2134' FNL, 2198' FWL



EQUITABLE RESOURCES ENERGY CO.
BALCRON MONUMENT FEDERAL #22-14J
SECTION 14, T9S, R16E, S.L.B.&M.



REFERENCE POINTS

150' SOUTHEAST 5594.10'
 200' SOUTHEAST 5598.55'
 200' SOUTHWEST 5603.80'
 250' SOUTHWEST 5606.31'

APPROXIMATE YARDAGES

CUT = 6390 Cu. Yds.
 FILL = 2070 Cu. Yds.
 PIT = 1,940 Cu. Yds.
 6" TOPSOIL = 900 Cu. Yds.

SURVEYED BY: G.S. J.S.
DRAWN BY: R.E.H.
DATE: 11-4-94
SCALE: 1" = 50'
FILE: 22-14J

Tri State
 Land Surveying, Inc.
 (801) 781-2501
 38 WEST 100 NORTH VERNAL, UTAH 84078

BALCRON OIL

43-012-31489

Balcron Monument Federal #22-14J

SE NW Section 14, T9S, R16E, SLB&M

Duchesne County, Utah

CONFIDENTIAL

PALEONTOLOGY REPORT

WELLPAD LOCATION AND ACCESS ROAD

BY

ALDEN H. HAMBLIN
PALEONTOLOGIST
235 EAST MAIN
VERNAL, UTAH 84078

DECEMBER 29, 1994

RESULTS OF PALEONTOLOGY SURVEY AT BALCRON MONUMENT FEDERAL #22-14J, SE, NW,
Section 14, T9S, R16E, SLB&R, DUCHESNE COUNTY, UTAH.

Description of Geology and Topography-

This well location is approximately 10 miles south and 2 miles west of Myton, Utah. It is located in a small flat bottom valley about 1/4 mile south of Castle Peak Draw. The proposed access road follows the proposed road for #32-14J for .2 mile then branches west .2 mile to the well location. The valley is composed of interbedded tan sandstone and green and brick red mudstone.

All rock outcrops in the area are of the Upper Eocene Uinta Formation, known for its fossil vertebrate fauna of mammals, turtles, crocodilians, and occasional fish remains and plant impressions.

Paleontological material found -

There are a few weathered turtle shell fragments near the proposed road just after it branches off toward the wellpad and drops into a wash.

No vertebrate fossils were found on the proposed wellpad.


Recommendations-

No recommendations are made for this location.

Alden H. Hamblin


Date December 29, 1994

PALEONTOLOGY LOCALITY Data Sheet					Page 1 of 1 plus map										
					State Local. No. 42 DC204V										
					Agency No. BALCRON MONUMENT BUTTE										
					Temp. No FEDERAL #22-14J										
1. Type of locality												Other _____			
Invertebrate		Plant		Vertebrate		X		Trace							
2. Formation: UINTA				Horizon: Lower (B)				Geologic Age: Late Eocene							
3. Description of Geology and Topography: The well is located in a small flat bottom valley about 1/4 mile south of Castle Peak Draw. The proposed access road follows the proposed road for #32-14J for .2 mile then branches west .2 mile to the well location. The valley is composed of interbedded tan sandstone and green and brick red mudstone. All rock outcrops in the area are of the Upper Eocene Uinta Formation, known for its fossil vertebrate fauna of mammals, turtles, crocodilians, and occasional fish remains and plant impressions.															
4. Location of Outcrop: 10 miles south and 2 miles west of Myton, Utah.															
5. Map Ref.		USGS Quad		Myton SE, Utah				Scale		7.5 Min		Edition		1964	
NE1/4		of		SE1/4		of		NW1/4		of Sectn		14 T 9 S R		16E Meridn SLB	
6. State: UTAH				County: DUCHESNE COUNTY				BLM/FS District: VERNAL- DIAMOND MT.							
7. Specimens Collected and Field Accession No. NONE															
8. Repository:															
9. Specimens Observed and Disposition: There are a few weathered turtle shell fragments near the proposed road just after it branches off toward the wellpad and drops into a wash.															
10.Owner:															
Private		State		BLM		X		US FS		NPS		IND		MIL OTHR	
11.Recommendations for Further Work or Mitigation: NONE															
12.Type of Map Made by Recorder:															
13.Disposition of Photo Negatives:															
14.Published References: Hamblin, A. H., 1992, Paleontology Report on the Monument Butte EA Study Area, for Mariah Associates, Laramie, Wyoming. Hamblin, A. H., 1994, Paleontology Report on the Monument Butte Expansion EA Study area, for Mariah Associates, Laramie, Wyoming. Hamblin, A. H., 1987, Paleogeography and paleontology of the Myton Pocket, Uinta Basin, Utah (Uinta Formation - Upper Eocene): BYU Geology Studies vol. 34, no. 1, p. 33-60.															
15.Remarks:															
16.Sensitivity:		Critical				Significant				Important		X		Insignificant	
17.Recorded by: Alden Hamblin, Paleontologist								Date: December 11, 1994							



EQUITABLE RESOURCES CO.

BALCRON MONUMENT FEDERAL #22-14J
SECTION 14, T9S, R16E, S.L.B.&M.
TOPO "B"



SCALE: 1" = 2000'

Tri State
Land Surveying, Inc.
 (801) 781-2501
 38 WEST 100 NORTH VERNAL, UTAH 84078

ABSTRACT

An intensive cultural resource evaluation has been conducted for Balcron Oil Company of ten proposed well locations and access routes (Balcron Monument Federal wells #42-12J, 11-7J, 41-12J, 42-14J, 32-14J, 22-14J, 24-25, 34-25, 43-26 and 14-26). These evaluated locations are situated on federally administered lands located in the Monument Buttes and Pleasant Valley localities of Duchesne and Uintah Counties, Utah. This evaluation involved a total of 135.15 acres, of which 100 acres are associated with the well pads and an additional 35.15 acres are associated with access road rights-of-way. One additional well included in this report, (Monument Federal 12-7J) was previously inventoried in a forty acre intensive zone (inventory #013-163, Vernal BLM). The well pad and access road for that location have already been constructed. These evaluations were conducted by F.R. Hauck and Glade Hadden of AERC on December 15 and 20, 1994.

No previously recorded significant or National Register eligible cultural resources will be adversely affected by the proposed developments.

No newly identified cultural resource activity loci of either historic or prehistoric origin were discovered and recorded during the examinations.

Two isolated artifacts were noted during the investigations. An isolated Rose Spring style projectile point (Isolate 1461G/X1, see Figure 1) was recovered from the disturbance zone of well # 43-26 (see Map 3). A non-diagnostic biface chopping tool was discovered but not collected near the well pad for well # 42-12J. This tool is similar in appearance to others found in the area (Hauck and Hadden 1994d).

AERC recommends project clearance based on adherence to the stipulations noted in the final section of this report.

**CULTURAL RESOURCE EVALUATION
OF PROPOSED WELL LOCATIONS AND ACCESS ROUTES
IN THE MONUMENT BUTTES AND
PLEASANT VALLEY LOCALITIES
OF DUCHESNE & UINTAH COUNTIES, UTAH**


Report Prepared for Balcron Oil Company

**Dept. of Interior Permit No.: UT-94-54937
AERC Project 1461 (BLCR-94-11)**

Utah State Project No.: UT-94-AF-775b

**Principal Investigator
F. Richard Hauck, Ph.D.**

**Authors of the Report
F. Richard Hauck & Glade V Hadden**



**ARCHEOLOGICAL-ENVIRONMENTAL RESEARCH
CORPORATION (AERC)**

**181 North 200 West, Suite 5
P.O. Box 853
Bountiful, Utah 84011-0853**

December 30, 1994

TABLE OF CONTENTS

	page
Abstract	ii
Table of Contents	iii
List of Maps of the Project Area	iv
General Information	1
Project Location	1
Environmental Description	6
Previous Research in the Locality	7
File Search	7
Prehistory and History of the Cultural Region.	7
Site Potential in the Project Development Zone	7
Field Evaluations	8
Methodology	8
Site Significance Criteria	8
Results of the Inventory	9
Conclusion and Recommendations	10
References	11

LIST OF MAPS OF THE PROJECT AREA

	page
MAP 1: General Balcron Project Locality in Duchesne and Uintah Counties, Utah	2
MAP 2: Cultural Resource Survey of Balcron Units 11-7J, 12-7J, 22-14J, 32-14J, 41-12J, 42-12J, and 42-14J in the Monument Buttes Locality of Duchesne County Utah . . .	3
MAP 3: Cultural Resource Survey of Balcron Units 24-25, 34-25, and 43-26 in the Pleasant Valley Locality of Uintah County, Utah .	4
MAP 4: Cultural Resource Survey of Balcron Unit 14-26 in the Monument Buttes Locality of Duchesne County, Utah . . .	5

LIST OF ARTIFACTS

	page
FIGURE 1: Isolate 1461G/x1	9

GENERAL INFORMATION

On December 15 and 20, 1994, AERC archaeologists F.R. Hauck and Glade Hadden conducted an intensive cultural resource evaluation for Balcron Oil Company of Billings, Montana. This examination involved ten proposed well locations and associated access roads (Balcron Monument Federal Units 42-12J, 11-7J, 41-12J, 42-14J, 32-14J, 22-14J, 24-25, 14-26, 34-25, 43-26 and 14-26), and an additional well (Balcron Monument Federal 12-7J which has been constructed and previously inventoried in a forty acre intensive survey zone (inventory 013-163, Vernal BLM). The project area is in the Monument Buttes and Pleasant Valley localities south east of Myton, Utah (see Map 1). Some 135.15 acres were examined which include 100 acres associated with the well pads and some 35.15 acres associated with the access routes, all of which are situated on federal lands administered by the Vernal District of the Bureau of Land Management, Diamond Mountain Resource Area, Vernal, Utah.

The purpose of the field study and this report is to identify and document cultural site presence and assess National Register potential significance relative to established criteria (cf., Title 36 CFR 60.6). The proposed development of these well locations and associated access routes requires an archaeological evaluation in compliance with U.C.A. 9-8-404, the Federal Antiquities Act of 1906, the Reservoir Salvage Act of 1960-as amended by P.L. 93-291, Section 106 of the National Historic Preservation Act of 1966-as amended, the National Environmental Policy Act of 1969, the Federal Land Policy and Management Act of 1979, the Archaeological Resources Protection Act of 1979, the Native American Religious Freedom Act of 1978, the Historic Preservation Act of 1980, and Executive Order 11593.

In addition to documenting cultural identity and significance, mitigation recommendations relative to the preservation of cultural data and materials can be directed to the Bureau of Land Management, Vernal District Office and to the State Antiquities Section.

Project Location

The project location is in the Monument Buttes locality of Duchesne County, and the Pleasant Valley locality of Uintah County. All of the evaluated wells and access routes are situated on the Myton SE and Pariette Draw SW 7.5 minute topographic quads (see Maps).


Balcron Monument Federal #11-7J is situated in the NW quarter of the NW quarter of Section 7, Township 9 South, Range 17 East SLBM, together with ca. 0.3 miles of access route (see Map 2).

Balcron Monument Federal #12-7J is situated in the SW quarter of the NW quarter of Section 7, Township 9 South, Range 17 East SLBM (see Map 2).

Balcron Monument Federal #41-12J is situated in the NE quarter of the NE quarter of Section 12, Township 9 South, Range 16 East SLBM, together with ca. 0.4 miles of access route (see Map 2).

**MAP 1: GENERAL BALCRON PROJECT
LOCALITY IN DUCHESNE AND UINTAH
COUNTIES OF NORTHWESTERN UTAH**

PROJECT: BLCR-94 - 11
SCALE: see below
QUAD: UG & MS Map 43
DATE: 12-30-94



UTAH

T. multiple


R. multiple

Meridian: Salt Lake B & M

**(After PHYSIOGRAPHIC SUBDIVISIONS
OF UTAH by W.L. Stokes)**

**MAP 2: CULTURAL RESOURCE SURVEY
OF BALCRON UNITS 11-7J, 12-7J,
22-14J, 32-14J, 41-12J, 42-12J, and
42-14J IN THE
MONUMENT BUTTES LOCALITY OF
DUCHESE COUNTY, UTAH**

PROJECT: BLCR - 94 - 11
SCALE: 1: 24,000
QUAD: Myton SE, Utah
DATE: 12 - 30 - 94



LEGEND:



UTAH

T. 9 South


R. 16 East

Meridian: Salt Lake B & M

Existing Well Location

Survey Plot

Access Route




**MAP 3: CULTURAL RESOURCE SURVEY
OF BALCRON UNITS 24-25, 34-25, and
43-26 IN THE PLEASANT VALLEY
LOCALITY OF UINTAH COUNTY, UTAH**

PROJECT: BLCR-94-11


SCALE: 1: 24,000

QUAD: Pariette Draw SW, Utah

DATE: 12 - 30 - 94



LEGEND:



T. 8 South

R. 17 East

Meridian: Salt Lake B & M

Isolated Artifact

Survey Plot

Access Route



Balcron Monument Federal #42-12J is situated in the SE quarter of the NE quarter of Section 12, Township 9 South, Range 16 East SLBM, together with ca. 0.3 miles of access route (see Map 2).

Balcron Monument Federal #22-14J is situated in the SE quarter of the NW quarter of Section 14, Township 9 South, Range 16 East SLBM, together with ca. 0.1 miles of access route (see Map 2).

Balcron Monument Federal #32-14J is situated in the SW quarter of the NE quarter of Section 14, Township 9 South, Range 16 East SLBM, together with ca. .03 miles of access route (see Map 2).

Balcron Monument Federal #42-14J is situated in the SE quarter of the NE quarter of Section 14, Township 9 South, Range 16 East SLBM, together with ca. 0.6 miles of access route (see Map 2).

Balcron Monument Federal #24-25 is situated in the SE quarter of the SW quarter of Section 25, Township 8 South, Range 17 East SLBM, together with ca. 0.1 miles of access route (see Map 3).

Balcron Monument Federal #34-25 is situated in the SW quarter of the SE quarter of Section 25, Township 8 South, Range 17 East SLBM, together with ca. 0.4 miles of access route (see Map 3).

Balcron Monument Federal #43-26 is situated in the NE quarter of the SE quarter of Section 26, Township 8 South, Range 17 East SLBM, together with ca. 0.2 miles of access route (see Map 3).

Balcron Monument Federal #14-26 is situated in the SW quarter of the SW quarter of Section 26, Township 8 South, Range 16 East SLBM, together with ca. 0.2 miles of access route (see Map 4).

Environmental Description

The project area is within the 5000 to 5500 foot elevation zone above sea level. Open rangeland terrain and eroded Eocene lakebed surfaces are associated with the project localities.

The vegetation in the project area includes *Chrysothamnus* spp. *Artemisia* spp., *Sarcobatus vermiculatus*, *Ephedra viridis*, *Cercocarpus* spp. *Atriplex canescens*, and a variety of grasses.

The geological associations within the project area consist of fluvial lake deposits which correlate with the Uinta Formation which is of Tertiary age.

PREVIOUS RESEARCH IN THE LOCALITY

File Search

A records search of the site files and maps at the Antiquities Section of the State Historic Preservation Office in Salt Lake City was conducted on December 19, 1994. A similar search was conducted in the Vernal District Office of the BLM on December 15, 1994. The National Register of Historic Places has been consulted and no registered historic or prehistoric properties will be affected by the proposed developments.

A variety of known cultural sites are situated in the Monument Buttes / Castle Peak Draw/ Eight Mile Flat/ Pariette Draw localities. Many of these prehistoric resources were identified and recorded by AERC during the Mapco River Bend survey (Hauck and Norman 1980). Other sites have been located and recorded by AERC and other archaeologists and consultants during oil and gas exploration inventories (cf. Fike and Phillips 1984, Hauck and Weder 1989).

Prehistory and History of the Cultural Region

Currently available information indicates that the Northern Colorado Plateau Cultural Region has been occupied by a variety of cultures beginning perhaps as early as 10,000 B.C. These cultures, as identified by their material remains, demonstrate a cultural developmental process that begins with the earliest identified Paleoindian peoples (10,000 -- 7,000 B.C.) and extends through the Archaic (ca. 7,000 B.C. -- A.D. 300), and Formative (ca. A.D. 400 -- 1100) Stages, and the Late Prehistoric-Protohistoric periods (ca. A.D. 1200 -- 1850) to conclude in the Historic-Modern period which was initiated with the incursion of the Euro-American trappers, explorers, and settlers. Basically, each cultural stage -- with the exception of the Late Prehistoric hunting and gathering Shoshonean bands -- features a more complex life-way and social order than occurred during the earlier stage of development (Hauck 1991:53). For a more comprehensive treatment of the prehistory and history of this region see Archaeological Evaluations in the Northern Colorado Plateau Cultural Area (Hauck 1991).

Site Potential in the Project Development Zone

Previous archaeological evaluations in the general project area have resulted in the identification and recording of a variety of cultural resource sites having eligibility for potential nomination to the National Register of Historic Places (NRHP). The majority of these sites are lithic scatters containing cobble reduction materials. Many of these quarry sites are of the "Tap and Test" variety, and extend for tens or hundreds of meters. Open occupations are also frequently being identified in this locality. Sites associated with the open rangeland generally appear to have been occupied during the Middle Plains Archaic Stage with occasional indications of Paleoindian activity based on the recovery of isolated Plano style projectile points. The north-south drainage canyons appear to contain the majority of Late Prehistoric (Numa) sites probably because those canyon floors were transportation corridors and convenient pastures for the Ute

horse herds. Evidence of Formative Stage occupation, i.e., Fremont, is rarely observed in the rangeland environment but is common within the Green River and White River canyons and their primary tributary canyons.

Site density in certain portions of the region appears to range from one to four sites per section. These densities increase in the canyon bottoms due to Ute rock art loci. Recent evaluations indicate that the site densities may reach 8 to 12 sites per section in certain localities on the upper benches which were apparently favored for hunting, lithic resource procurement, and camping. Prehistoric sites on the rangeland benches appear to be associated with water courses and aeolian deposits.

FIELD EVALUATIONS

Methodology

Intensive evaluations consisted of the archaeologists walking a series of 10 to 20 meter-wide transects across a 10 acre area associated with each ten acre well pad area. Access routes are evaluated by the archaeologists walking a pair of 10 to 15 meter-wide transects on either side of the flagged access route rights of way. Thus, a 30 meter-wide or 100 foot-wide corridor (ca. 35.15 acres) was examined for the various proposed access roads, in addition to the 100 acres inventoried on the well pads.

Observation of cultural materials results in intensive examinations to determine the nature of the resource (isolate or activity locus). The analysis of each specific cultural site results in its subsequently being sketched, photographed, and appropriately recorded on standard IMACS forms. Cultural sites are then evaluated for significance utilizing the standards described below and mitigation recommendations are considered as a means of preserving significant resources which may be situated within the development zone.

Site Significance Criteria

Prehistoric and historic cultural sites which can be considered as eligible for nomination to the National Register of Historic Places have been outlined as follows in the National Register's Criteria for Evaluation as established in Title 36 CFR 60.6:

The quality of significance in American ... archaeology ... and culture is present in ... sites ... that possess integrity of location, design, setting, materials, workmanship, feeling, and association and:

- a. That are associated with events that have made a significant contribution to the broad patterns of our history; or*
- b. that are associated with the lives of persons significant in our past; or*
- c. that embody the distinctive characteristics of a type, period, or method of construction ... ; or*
- d. that have yielded, or may be likely to yield, information important in prehistory or history.*

In addition to satisfying one or more of these general conditions, a significant cultural resource site in Utah will generally be considered as being eligible for inclusion in the National Register if it should advance our current state of knowledge relating to chronology, cultural relationships, origins, and cultural life ways of prehistoric or historic groups in the area.

In a final review of any site's cultural significance, the site must possess integrity and at least one of the above criteria to be considered eligible for nomination to the National Record of Historic Places.

Results of the Inventory

No prehistoric or historic cultural resource activity loci were observed and recorded during the archaeological evaluations.

No previously identified and recorded significant or National Register sites were noted or recorded during the survey.

One diagnostic isolated artifact was collected during the evaluation. Isolate 1461G/x1 is a Rose Spring style projectile point (see Figure 1) collected from the disturbance zone of well # 43-26 (see Map 3). A detailed evaluation of the locality failed to yield any identifiable features or cultural contexts that would demonstrate the presence of an archaeological locus. A single non-diagnostic tool was noted in the area of well 42-12J. This tool was a simple chopper constructed by bifacially removing several flakes from one end of a hand-sized cobble. The occurrence of this tool fits a previously noted pattern (Hauck and Hadden 1994d), and may be related to the ambush hunting and subsequent butchering of large game animals, possibly during the Archaic period. A detailed evaluation of the locality failed to yield any identifiable features or cultural contexts that would demonstrate the presence of an archaeological locus.





FIGURE 1
Isolate 1461G/x1
(Actual Size)

CONCLUSION AND RECOMMENDATIONS

No known significant cultural resources will be adversely impacted during the development and operation of the Balcron Well Units as evaluated during this AERC project.

AERC recommends that a cultural resource clearance be granted to Balcron Oil Company relative to the development of these proposed drilling locations and the associated access routes based upon adherence to the following stipulations:

1. all vehicular traffic, personnel movement, construction and restoration operations should be confined to the flagged areas and corridors examined as referenced in this report, and to the existing roadways;
2. all personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area; and
3. the authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.



F. Richard Hauck, Ph.D.
President and Principal Investigator

REFERENCES

Fike, Richard E. and H. Blaine Phillips II

- 1984 "A Nineteenth Century Ute Burial from Northeast Utah." Cultural Resource Series No. 16, Bureau of Land Management, Salt Lake City.

Hauck, F. Richard

- 1981 Cultural Resource Inventory of Nine Proposed Well Locations and Access Roads in the Coyote Basin Locality of Uintah County, Utah, and in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Diamond Shamrock, DS-81-2, Archeological-Environmental Research Corporation, Bountiful.
- 1982 Cultural Resource Inventory of Five Proposed Well Locations and Access Roads in the Eightmile Flat and Castle Peak Localities of Uintah and Duchesne Counties, Utah. Report Prepared for Diamond Shamrock, DS-82-5, Archaeological-Environmental Research Corporation, Bountiful.
- 1984a Excavation (in) "A Nineteenth Century Ute Burial from Northeast Utah." Cultural Resource Series No. 16, Bureau of Land Management, (Richard E. Fike and Blaine Phillips II editors and principal authors) Salt Lake City.
- 1984b Cultural Resource Evaluations of Seven Proposed Well Locations Situated in the Castle Peak Draw Locality of Uintah County, Utah. Report Prepared for Overthrust Oil and Royalty Company, OORC-84-1, Archaeological-Environmental Research Corporation, Bountiful.
- 1991 Archaeological Evaluations on the Northern Colorado Plateau Cultural Area, AERC Paper No. 45, Archeological-Environmental Research Corporation, Bountiful.
- 1992a Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-2, Archeological-Environmental Research Corporation, Bountiful.
- 1992b Addendum to Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-4, Archeological-Environmental Research Corporation, Bountiful.

- 1992c Cultural Resource Evaluations of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-5, Archeological-Environmental Research Corporation, Bountiful.
- 1992d Cultural Resource Evaluation of a Proposed Water Pipeline Corridor in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-6, Archeological-Environmental Research Corporation, Bountiful.
- 1992e Cultural Resource Evaluation of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-8, Archeological-Environmental Research Corporation, Bountiful.
- 1993a Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-1, Archeological-Environmental Research Corporation, Bountiful.
- 1993b Addendum to Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-2, Archeological-Environmental Research Corporation, Bountiful.
- 1993c Cultural Resource Evaluation of a Pipeline Corridor Situated in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-3, Archeological-Environmental Research Corporation, Bountiful.

Hauck, F. Richard and Glade V Hadden

- 1993a Cultural Resource Evaluation of Seven Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-4, Archaeological-Environmental Research Corporation, Bountiful.
- 1993b Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-5, Archaeological-Environmental Research Corporation, Bountiful.
- 1993c Cultural Resource Evaluation of Eight Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil

Company, BLCR-93-9, Archaeological-Environmental Research Corporation, Bountiful.

1993d Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-10, Archaeological-Environmental Research Corporation, Bountiful.

1993e Cultural Resource Evaluation of Seven Proposed Wells in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-11, Archaeological-Environmental Research Corporation, Bountiful.

1994a Cultural Resource Evaluation of Eight Proposed Wells in the Pleasant Valley Locality of Uintah County, Utah. Report prepared for Balcron Oil Company, BLCR-94-3 Archaeological-Environmental Research Corporation, Bountiful.

1994b Cultural Resource Evaluation of Proposed Water Injection Line Lateral Segments in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-94-4, Archaeological-Environmental Research Corporation, Bountiful.

1994c Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Pariette Draw - Castle Peak Draw - Eight Mile Flat Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-94-9, Archaeological-Environmental Research Corporation, Bountiful.

1994d Cultural Resource Evaluation of Proposed Well Locations and Access Routes in the Castle Peak Draw and Eightmile Flat Localities of Duchesne and Uintah Counties, Utah. Report Prepared for Balcron Oil Company, BLCR-94-10, Archaeological-Environmental Research Corporation, Bountiful.

Hauck, F. Richard and Norman, V. Garth

1980 Final Report on the Mapco River Bend Cultural Mitigation Study. AERC Paper No. 18, of the Archeological-Environmental Research Corporation, Bountiful.

Hauck, F. Richard and Dennis Weder

1989 Pariette Overlook -- A Paleo-Indian Quarry Site in the Pariette Draw Locality of Uintah County, Utah. AERC Paper No. 42, of the Archeological-Environmental Research Corporation, Bountiful.

Stokes, W. L.

1977 Physiographic Subdivisions of Utah. Map 43, Utah Geological and Mineral Survey, Salt Lake.

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 12/20/94

API NO. ASSIGNED: 43-013-31489

WELL NAME: BALCRON MONUMENT FED 22-14J
OPERATOR: EQUITABLE RESOURCES (N9890)

PROPOSED LOCATION:

SE NW 14 - T09S - R16E
SURFACE: 2134-FNL-2198-FWL
BOTTOM: 2134-FNL-2198-FWL
DUCHESNE COUNTY
MONUMENT BUTTE FIELD (105)

LEASE TYPE: FED
LEASE NUMBER: U-096547

PROPOSED PRODUCING FORMATION: GRRV

INSPECT LOCATION BY: / /

TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Federal ☒ State ☐ Fee ☐
(Number 5547188)
☒ Potash (Y/N)
☒ Oil shale (Y/N)
☒ Water permit
(Number PRIVATE WELL)
☒ RDCC Review (Y/N)
(Date: _____)

LOCATION AND SITING:

☒ R649-2-3. Unit: UTU72068A
☐ R649-3-2. General.
☐ R649-3-3. Exception.
☐ Drilling Unit.
Board Cause no: _____
Date: _____

COMMENTS: _____

STIPULATIONS: _____

STATE OF UTAH

Operator: EQUITABLE RESOURCES	Well Name: MONUMENT BUTTE FED 2
Project ID: 43-013-31489	Location: SEC. 14 - T09S - R16E

Design Parameters:

Mud weight (8.90 ppg) : 0.462 psi/ft
 Shut in surface pressure : 2276 psi
 Internal gradient (burst) : 0.056 psi/ft
 Annular gradient (burst) : 0.000 psi/ft
 Tensile load is determined using buoyed weight
 Service rating is "Sweet"

Design Factors:

Collapse : 1.125
 Burst : 1.00
 8 Round : 1.80 (J)
 Buttress : 1.60 (J)
 Other : 1.50 (J)
 Body Yield : 1.50 (B)

Length (feet)		Size (in.)	Weight (lb/ft)	Grade	Joint	Depth (feet)	Drift (in.)	Cost	
1	5,600	5.500	15.50	K-55	ST&C	5,600	4.825		
	Collapse Load Strgth S.F. (psi) (psi)			Burst Load (psi)	Min Int Yield Strgth (psi)		Tension Load Strgth S.F. (kips) (kips)		
1	2589	4040	1.560	2589	4810	1.86	74.99	222	2.96 J

Prepared by : KMH, Salt Lake City, UT
 Date : 03-07-1995
 Remarks :

Minimum segment length for the 5,600 foot well is 1,000 feet.
 SICP is based on the ideal gas law, a gas gravity of 0.69, and a mean gas
 temperature of 102°F (Surface 74°F , BHT 130°F & temp. gradient 1.000°/100 ft.)
 The mud gradient and bottom hole pressures (for burst) are 0.462 psi/ft and
 2,589 psi, respectively.

NOTE: The design factors used in this casing string design are as shown above. As a general guide-
 line, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with
 evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body
 Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and
 Kemler curve. Engineering responsibility for use of this design will be that of the purchaser.
 Costs for this design are based on a 1987 pricing model. (Version 1.06)

T 8 S

ABLE RESOURCES ENERGY
ON MONUMENT BUTTE
H UNIT WATERFLOOD
ESNE COUNTY T9S, R 16 & 17 E

T 9 S

41-12J

11-7J

42-12J

12-7J

12-14J

22-14J

32-14J

42-14J

R 16 E

R 17 E



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

March 7, 1995

Equitable Resources Energy Company
P.O. Box 21017
Billings, Montana 59104

Re: Balcron Monument Federal #22-14J Well, 2134' FNL, 2198' FWL, SE NW, Sec. 14, T. 9 S., R. 16 E., Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Admin. R. 649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-31489.

Sincerely,


R. J. Firth
Associate Director

ldc

Enclosures

cc: Duchesne County Assessor

Bureau of Land Management, Vernal District Office

WAPD



Operator: Equitable Resources Energy Company

Well Name & Number: Balcron Monument Federal #22-14J

API Number: 43-013-31489

Lease: Federal #U-096547

Location: SE NW Sec. 14 T. 9 S. R. 16 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5340.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews or Mike Hebertson at (801)538-5340.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

b. TYPE OF WELL

OIL WELL ☒

GAS WELL ☐

OTHER

SINGLE ZONE ☐

MULTIPLE ZONE ☐

2. NAME OF OPERATOR

Equitable Resources Energy Company, Balcron Oil Division

3. ADDRESS OF OPERATOR

P.O. Box 21017; Billings, MT 59104

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

SE NW Section 14, T9S, R16E
At proposed prod. zone

2134' FNL, 2198' FWL

43-012-31489

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately 13 miles southwest of Myton, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

16. NO. OF ACRES IN LEASE

17. NO. OF ACRES ASSIGNED
TO THIS WELL

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

19. PROPOSED DEPTH

5,600'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

GL 5594.3'

22. APPROX. DATE WORK WILL START*

3/1/95


23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
See EXHIBIT	"D" Drilling	Program/Casing	Design	

Operator intends to drill this well in accordance with the attached permit. A listing of EXHIBITS is also attached.

SELF CERTIFICATION: I hereby certify that I am authorized, by proper lease interest owner, to conduct these operations associated with the application. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Equitable Resources Energy Company as principal and Safeco Insurance Company of America as surety under BLM Bond No. MT 0576 (Nationwide Oil & Gas Bond #5547188) who will be responsible for compliance with all of the terms and conditions of that portion of the lease associated with this application.



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

Bobbie Schuman
Bobbie Schuman

TITLE

Regulatory and
Environmental Specialist

DATE

12-19-94

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

Mark R. Cleary

TITLE

ASSISTANT DISTRICT
MANAGER MINERALS

DATE

MAR 6 1995

CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED
TO OPERATING COPY.

*See Instructions On Reverse Side

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Equitable Resources Energy Company

Well Name & Number: Balcron Federal 22-14J

API Number: 43-013-31489

Lease Number: U-096547

Location: SENW Sec. 14 T. 9S R. 16E

NOTIFICATION REQUIREMENTS

- | | | |
|---------------------------------|---|---|
| Location Construction | - | at least forty-eight (48) hours prior to construction of location and access roads. |
| Location Completion | - | prior to moving on the drilling rig. |
| Spud Notice | - | at least twenty-four (24) hours prior to spudding the well. |
| Casing String and Cementing | - | at least twenty-four (24) hours prior to running casing and cementing all casing strings. |
| BOP and Related Equipment Tests | - | at least twenty-four (24) hours prior to initiating pressure tests. |
| First Production Notice | - | within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days. |

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

The Vernal District Office shall be notified, at least 24 hours prior to initiating the pressure tests, in order to have a BLM representative on location during pressure testing.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

The surface casing will need to be cemented with **neat cement**.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the Usable Water zone identified at \pm **1909 ft.** If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

The Vernal District Office shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to \pm **1709 ft.** and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with

43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours prior to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9. d.), and shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b. 4).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted following initial installation and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Wayne P. Bankert (801) 789-4170
Petroleum Engineer

Ed Forsman (801) 789-7077
Petroleum Engineer

BLM FAX Machine (801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

SURFACE USE PLAN OF OPERATION
Conditions of Approval (COAs)

Methods for Handling Waste Disposal

The reserve pit liner will be a minimum of 12 mil thickness and have sufficient bedding (straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc..., that could puncture the liner will be disposed of in the pit.

Plans for Reclamation of Location

In addition to recontouring the reserve pit and that portion of the location not needed for production facilities and operation. These areas will also be reseeded and returned to a vegetated condition as determined by the Authorized Officer of the BLM.

At time of abandonment the intent of reclamation will be to return the disturbed area to near natural conditions. Recontour the surface of the disturbed area to blend all cuts, fills, road berms, and borrow ditches to be natural in appearance with the surrounding terrain. Stockpiled topsoil will be spread over the surface, and the area revegetated to the satisfaction of the Authorized Officer of the BLM.

Additional Surface Conditions of Approval

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362, forty-eight (48) hours prior to construction activities, including installation of the pit liner.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.



EQUITABLE RESOURCES
ENERGY COMPANY


BALCRON OIL DIVISION

1601 Lewis Avenue
Billings, MT 59102

Office: (406) 259-7860
FAX: (406) 245-1365 ☐
FAX: (406) 245-1361 ☒

March 22, 1996

Utah Division of Oil, Gas and Mining
355 West North Temple
Salt Lake City, UT 84180



Gentlemen:

Effective April 1, 1996, our name will change from Equitable Resources Energy Company, Balcron Oil Division to Equitable Resources Energy Company. Attached is a sundry notice reflecting that change. To simplify paperwork, I have done one sundry notice with copies for each of the wells. To this letter I have attached a list of our wells for your ease in filing the sundry notices in the well files. This should be sufficient for your purposes.

I have the listings on a spreadsheet so if it would be easier for you to have them sorted differently (for example, the Montana Board of Oil and Gas prefers them sorted by API number), please give me a call at (406) 259-7860, extension 240 and I would be glad to provide a list to your specifications.

This change affects only our company name. The physical locations of our offices and the personnel remain the same. We will be changing our well signs and ask for your patience and cooperation as this will be done as soon as possible but may take some time since we do have so many properties at which to make the change.

If you have any questions, please do not hesitate to give me a call.

Sincerely,

Bobbie Schuman

Bobbie Schuman
Regulatory and
Environmental Specialist

/hs

Enclosures

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☐ GAS ☐ OTHER: See attached listing

2. Name of Operator:
Equitable Resources Energy Company, Balcron Oil Division

3. Address and Telephone Number:
1601 Lewis Avenue Avenue; Billings, MT 59102 (406) 259-7860

4. Location of Well
Footages: See attached listing

QQ, Sec., T., R., M.:

5. Lease Designation and Serial Number:

See attached listing

6. If Indian, Allottee or Tribe Name:

n/a

7. Unit Agreement Name:

See attached listing

8. Well Name and Number:

See attached listing

9. API Well Number:

See attached listing

10. Field and Pool, or Wildcat:

See attached listing

County: See attached list

State: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT (Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other | |

Approximate date work will start

SUBSEQUENT REPORT (Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other | Operator name change |

Date of work completion

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Effective April 1, 1996, operator will change its name from Equitable Resources Energy Company, Balcron Oil Division TO: Equitable Resources Energy Company. Physical location of the operator remains as: 1601 Lewis Avenue; Billings, MT 59102 (406) 259-7860, FAX: (406) 145-1361. This is to report the operator name change only. It affects the wells on the attached listing.

APR - 8 1996

13.

Name & Signature:

Bobbie Schuman
Bobbie Schuman

Title:

Regulatory and

Environmental Specialist Date: March 27, 1996

(This space for State use only)

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Routing:

1	LEC 7-SJ
2	DEC 58-FILE
3	VLD (GIL) 2/2
4	RJE
5	IEC
6	FILM

Attach all documentation received by the division regarding this change.
 Initial each listed item when completed. Write N/A if item is not applicable.

- ☐ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ~~XXX~~ Operator Name Change Only

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 4-1-96)

TO (new operator)	<u>EQUITABLE RESOURCES ENERGY COEROM</u> (former operator)	<u>EQUITABLE RESOURCES ENERGY CO</u>
(address)	<u>1601 LEWIS AVE</u>	(address) <u>BALCRON OIL DIVISION</u>
	<u>BILLINGS MT 59102-4126</u>	<u>1601 LEWIS AVE</u>
		<u>BILLINGS MT 59102-4126</u>
phone	<u>(406) 259-7860</u>	phone <u>(406) 259-7860</u>
account no.	<u>N9890</u>	account no. <u>N9890</u>

Well(s) (attach additional page if needed):

Name: **SEE ATTACHED**	API: <u>43-013-31489</u>	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____

OPERATOR CHANGE DOCUMENTATION

- Yec 1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form). (Rec'd 4-4-96 & 4-8-96)
- N/A 2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form).
- N/A 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes/no) ____ If yes, show company file number: _____.
- * 4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of Federal and Indian well operator changes should take place prior to completion of steps 5 through 9 below.
- Yec 5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) ~~for each well listed above.~~ (4-10-96)
- Yec 6. Cardex file has been updated for each well listed above. (4-11-96)
- Yec 7. Well file labels have been updated for each well listed above. (4-11-96)
- Yec 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission. (4-10-96)
- Yec 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- Yes 1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
- N/A 2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.

BOND VERIFICATION (Fee wells only) # 5578314 (\$80,000) Secured Ins. Co. (Bond Rider In Progress)

- Yes 1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
2. A copy of this form has been placed in the new and former operators' bond files.
- N/A 3. The former operator has requested a release of liability from their bond (yes/no) . Today's date 19 . If yes, division response was made by letter dated 19 .

LEASE INTEREST OWNER NOTIFICATION RESPONSIBILITY

- N/A 1. (Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated 19 , of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
- 4/26/96 2. Copies of documents have been sent to State Lands for changes involving State leases.
Sent to Ed Bonner - Trust Lands

FILMING

- VB 1. All attachments to this form have been microfilmed. Date: June 03 1997.

FILING

1. Copies of all attachments to this form have been filed in each well file.
2. The original of this form and the original attachments have been filed in the Operator Change file.

COMMENTS

9/6/04/10 BLM/BIA "Formal approval not necessary"

Record#	OPERATOR	well_name	API_NUMBER	SECTION	TOWNSHIP	RANGE	DATEAPPRVD
1937	EQUITABLE RESOURCES	BALCRON MONUMENT FEDERAL 14-4	43-013-31430	04	09S	16E	12/20/93
2282	EQUITABLE RESOURCES	BALCRON MONUMENT FED 12-14J	43-013-31488	14	09S	16E	03/27/95
→2283	EQUITABLE RESOURCES	BALCRON MONUMENT FED 22-14J	43-013-31489	14	09S	16E	03/07/95
2284	EQUITABLE RESOURCES	BALCRON MONUMENT FED 32-14J	43-013-31490	14	09S	16E	03/07/95
2285	EQUITABLE RESOURCES	BALCRON MONUMENT FED 42-14J	43-013-31491	14	09S	16E	04/20/95
2375	EQUITABLE RESOURCES	BALCRON MONUMENT FEDERAL 14-26	43-013-31512	26	08S	16E	04/20/95
2472	EQUITABLE RESOURCES	BALCRON MON FED 11-10-9-17Y	43-013-31534	10	09S	17E	/ /
2609	EQUITABLE RESOURCES	MONUMENT STATE 23-16-9-17B	43-013-31578	16	09S	17E	01/03/96
2613	EQUITABLE RESOURCES	MONUMENT FEDERAL 23-17-9-17B	43-013-31582	17	09S	17E	02/05/96
2614	EQUITABLE RESOURCES	MONUMENT FEDERAL 13-22-8-17Y	43-013-31583	22	08S	17E	02/22/96
2618	EQUITABLE RESOURCES	MONUMENT FEDERAL 32-22-8-17	43-013-31586	22	08S	17E	02/20/96
2619	EQUITABLE RESOURCES	MONUMENT FEDERAL 31-22-8-17	43-013-31587	22	08S	17E	02/20/96
2620	EQUITABLE RESOURCES	MONUMENT FEDERAL 33-22-8-17	43-013-31588	22	08S	17E	03/25/96
2621	EQUITABLE RESOURCES	MONUMENT FEDERAL 33-6-9-16Y	43-013-31589	06	09S	16E	04/15/96
2622	EQUITABLE RESOURCES	MONUMENT FEDERAL 31-10-9-17Y	43-013-31591	10	09S	17E	/ /
2623	EQUITABLE RESOURCES	MONUMENT FEDERAL 32-10-9-17Y	43-013-31592	10	09S	17E	02/22/96
2201	EQUITABLE RESOURCES	ASP FEDERAL 1	43-027-30033	12	16S	19W	04/27/95
2539	EQUITABLE RESOURCES	COBRA FEDERAL 42-35	43-027-30037	35	15S	19W	/ /
1942	EQUITABLE RESOURCES	BALCRON MONUMENT FEDERAL 41-26	43-047-32456	26	08S	17E	12/21/93
2099	EQUITABLE RESOURCES	BALCRON MONUMENT FEDERAL 42-26	43-047-32531	26	08S	17E	06/01/95
2264	EQUITABLE RESOURCES	BALCRON MONUMENT STATE 32-2	43-047-32609	02	09S	17E	12/29/94
2267	EQUITABLE RESOURCES	BALCRON MONUMENT STATE 34-2	43-047-32611	02	09S	17E	12/29/94
2376	EQUITABLE RESOURCES	BALCRON MONUMENT FEDERAL 43-26	43-047-32668	26	08S	17E	05/08/95
2481	EQUITABLE RESOURCES	BALCRON MON FEDERAL 23-24-8-17	43-047-32710	24	08S	17E	02/13/96
2625	EQUITABLE RESOURCES	MONUMENT FEDERAL 32-20-9-18Y	43-047-32725	20	09S	18E	02/06/96
2635	EQUITABLE RESOURCES	MONUMENT FED 41-35-9-18Y	43-047-32727	35	09S	18E	04/15/96
2636	EQUITABLE RESOURCES	MONUMENT FED 44-31-8-18Y	43-047-32728	31	08S	18E	/ /
2637	EQUITABLE RESOURCES	MONUMENT FEDERAL 43-19-9-18Y	43-047-32730	19	09S	18E	02/05/96


OH/Pending Status

UTAH

Balcron Monument Fed. #14-12J	Monument Butte	SW SW	12	9S	16E	Duchesne	UT	WIW	Green River	U-035521-A	43-013-31411	660' FSL, 660' FWL	Vernal	Jonah
Balcron Monument Fed. #14-15	Monument Butte	SW SW	15	9S	16E	Duchesne	UT	PND	Green River	U-017985	43-013-31381	772' FSL, 543' FWL	Vernal	
Balcron Monument Fed. #14-26	Monument Butte	SW SW	26	8S	16E	Duchesne	UT	PND	Green River	U-34346	43-013-31512	660' FSL, 660' FWL	Vernal	
Balcron Monument Fed. #14-3-9-17Y	Monument Butte	SW SW	3	9S	17E	Duchesne	UT	Oil	Green River	U-64381	43-013-31535	671' FSL, 792' FWL	Vernal	
Balcron Monument Fed. #14-4	Monument Butte	SW SW	4	9S	16E	Duchesne	UT	PND	Green River	U-73086	43-013-31430	719' FSL, 607' FWL	Vernal	
Balcron Monument Fed. #14-5	Monument Butte	SW SW	5	9S	17E	Duchesne	UT	Oil	Green River	U-020250	43-013-31385	556' FSL, 517' FWL	Vernal	Jonah
Balcron Monument Fed. #14-8	Monument Butte	SW SW	8	9S	17E	Duchesne	UT	Oil	Green River	UTU-74108	43-013-31398	660' FSL, 660' FWL	Vernal	Beluga
Balcron Monument Fed. #21-10-9-17Y	Monument Butte	NE NW	10	9S	17E	Duchesne	UT	Oil	Green River	U-65210	43-013-31537	807' FNL, 2120' FWL	Vernal	
Balcron Monument Fed. #21-14J	Monument Butte	NE NW	14	9S	16E	Duchesne	UT	WIW	Green River	U-096547	43-013-31421	518' FNL, 1850' FWL	Vernal	Jonah
Balcron Monument Fed. #21-17	Monument Butte	NE NW	17	9S	17E	Duchesne	UT	Oil	Green River	U-3563-A	43-013-31387	500' FNL, 1980' FWL	Vernal	Beluga
Balcron Monument Fed. #21-25	Undesignated	NE NW	25	8S	17E	Uintah	UT	Oil	Green River	U-67845	43-047-32528	748' FNL, 1964' FWL	Vernal	
Balcron Monument Fed. #22-12J	Monument Butte	SE NW	12	9S	16E	Duchesne	UT	Oil	Green River	U-096550	43-013-15796	2018' FNL, 2099' FWL	Vernal	Jonah
Balcron Monument Fed. #22-14J	Monument Butte	SE NW	14	9S	16E	Duchesne	UT	PND	Green River	U-096547	43-013-31489	2134' FNL, 2198' FWL	Vernal	Jonah
Balcron Monument Fed. #22-17	Monument Butte	SE NW	17	9S	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31429	1800' FNL, 1980' FWL	Vernal	Beluga
Balcron Monument Fed. #22-20-9-18Y	Monument Butte	SE NW	20	9S	18E	Uintah	UT	Oil	Green River	U-64917	43-047-32711	1980' FNL, 1980' FWL	Vernal	
Balcron Monument Fed. #22-22-8-17Y	Monument Butte	SE NW	22	8S	17E	Duchesne	UT	Oil	Green River	U-67845	43-013-31538	1945' FNL, 2030' FWL	Vernal	
Balcron Monument Fed. #22-5	Monument Butte	SE NW	5	9S	17E	Duchesne	UT	WIW	Green River	U-020252	43-013-31384	1853' FNL, 1980' FWL	Vernal	Jonah
Balcron Monument Fed. #23-11	Monument Butte	NE SW	11	9S	16E	Duchesne	UT	WIW	Green River	U-096550	43-013-31369	1787' FSL, 2147' FWL	Vernal	Jonah
Balcron Monument Fed. #23-15	Monument Butte	NE SW	15	9S	16E	Duchesne	UT	WIW	Green River	U-017985	43-013-31373	1724' FSL, 2078' FWL	Vernal	Jonah
Balcron Monument Fed. #23-24-8-17		NE SW	24	8S	17E	Uintah	UT	PND	Green River				Vernal	
Balcron Monument Fed. #23-25	Undesignated	NE SW	25	8S	17E	Uintah	UT	Oil	Green River	U-67845	43-047-32529	1927' FSL, 2139' FWL	Vernal	
Balcron Monument Fed. #23-5	Monument Butte	NE SW	5	9S	17E	Duchesne	UT	Oil	Green River	U-020252	43-013-31383	1816' FSL, 2057' FWL	Vernal	Jonah
Balcron Monument Fed. #24-12J	Monument Butte	SE SW	12	9S	16E	Duchesne	UT	Oil	Green River	U-035521-A	43-013-31409	539' FSL, 1777' FWL	Vernal	Jonah
Balcron Monument Fed. #24-25	Undesignated	SE SW	25	8S	17E	Uintah	UT	Oil	Green River	U-67845	43-047-32669	653' FSL, 2028' FWL	Vernal	
Balcron Monument Fed. #24-5	Monument Butte	SE SW	5	9S	17E	Duchesne	UT	WIW	Green River	U-020252	43-013-31375	765' FSL, 2243' FWL	Vernal	Jonah
Balcron Monument Fed. #24-6	Monument Butte	SE SW	6	9S	17E	Duchesne	UT	WIW	Green River	U-020252-A	43-013-31363	504' FSL, 1613' FWL	Vernal	Jonah
Balcron Monument Fed. #31-17	Monument Butte	NE NW	17	9S	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31428	660' FNL, 1980' FEL	Vernal	Beluga
Balcron Monument Fed. #31-1J	Monument Butte	NW NE	1	9S	16E	Duchesne	UT	Oil	Green River	U-33992	43-013-31413	660' FNL, 1980' FEL	Vernal	Jonah
Balcron Monument Fed. #31-25	Undesignated	NW NE	25	8S	17E	Uintah	UT	Oil	Green River	U-67845	43-047-32530	660' FNL, 1980' FEL	Vernal	
Balcron Monument Fed. #31-7J	Monument Butte	NW NE	7	9S	17E	Duchesne	UT	WIW	Green River	U-44426	43-013-31405	831' FNL, 1782' FEL	Vernal	Jonah
Balcron Monument Fed. #32-11	Monument Butte	SW NE	11	9S	16E	Duchesne	UT	WIW	Green River	U-096550	43-013-31386	2059' FNL, 1763' FEL	Vernal	Jonah
Balcron Monument Fed. #32-12J	Monument Butte	SW NE	12	9S	16E	Duchesne	UT	WIW	Green River	U-035521	43-013-31419	1805' FNL, 2139' FEL	Vernal	Jonah
Balcron Monument Fed. #32-14J	Monument Butte	SW NE	14	9S	16E	Duchesne	UT	PND	Green River	U-096547	43-013-31490	1980' FNL, 1980' FEL	Vernal	Jonah
Balcron Monument Fed. #32-15	Monument Butte	SW NE	15	9S	16E	Duchesne	UT	WIW	Green River	U-017985	43-013-31368	1868' FNL, 1993' FEL	Vernal	Jonah
Balcron Monument Fed. #32-17	Monument Butte	SW NE	17	9S	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31465	1880' FNL, 1980' FEL	Vernal	Beluga

CONFIDENTIAL

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT



FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Equitable Resources Energy Company

3. Address and Telephone No.

1601 Lewis Avenue; Billings, MT 59102 (406) 259-7860

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE NW Sec. 14-T9S-R16E

2134' FNL, 2198' FNL

5. Lease Designation and Serial No.

U-096547

6. If Indian, Allottee or Tribe Name

n/a

7. If Unit or CA, Agreement Designation

Jonah Unit

8. Well Name and No.

Balcon Mon. Fed. #22-145

9. API Well No.

43-013-31489

10. Field and Pool, or Exploratory Area

Monument Butte/Green River

11. County or Parish, State

Duchesne County, UTAH

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other Renew APD
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

The Federal Application for Permit to Drill (APD) this well expires: 3-7-96

Operator requests a one-year renewal of the APD.

Extend to
3/2/97
DTS

ORIGINAL: Bureau of Land Management (Vernal, UT)

COPY: Utah Division of Oil, Gas and Mining (Salt Lake City, UT)

14. I hereby certify that the foregoing is true and correct

Signed

Bobbie Schuman

Regulatory and

Title

Environmental Specialist

Date

March 6, 1996

(This space for Federal or State office use)

Approved by

Matthew

Title

Petroleum Engineer

Date

4/18/96



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Vernal District Office

170 South 500 East

Vernal, Utah 84078-2799

Phone: (801) 781-4400

Fax: (801) 781-4410


IN REPLY REFER TO:

3162

UT08300

April 28, 1997

Equitable Resources Energy Company
Attn: Bobbie Schuman
1601 Lewis Avenue
Billings MT 59104



43-013-31489

Re: Notification of Expiration
Well Balcron Monument Fed. 22-14J
Section 14, T9S, R16E
Lease No. U-096547

Dear Ms. Schuman:

The Application for Permit to Drill the above-referenced well was approved on March 6, 1995. Equitable Resources Energy Company requested an extension of the original APD approval for an additional year. The request was reviewed and the extension approved until March 6, 1997. According to our records, no known activity has transpired at the approved location. In view of the foregoing, this office is notifying you the approval of the referenced application has expired. If you intend to drill at this location at a future date, a new Application for Permit to Drill must be submitted.

This office requires a letter confirming that no surface disturbance has been made for this drill site. Any surface disturbance associated with the approved location of this well is to be rehabilitated. A schedule for this rehabilitation must be submitted to this office. Your cooperation in this matter is appreciated.

Sincerely,

Margie Herrmann
Legal Instruments Examiner

cc: State Div. OG&M

From: Don Staley
To: Marjie Herrman - BLM Vernal
Date: 5/2/97 1:54pm
Subject: RESCIND LETTERS

Hi Margie,

Let's see if this e-mail address really works!

I have a question for you. I just received copies of your rescind letters for

Balcron Monument Fed 42-14J	14-9S-16E
and	
Balcron Monument Fed 22-14J	14-9S-16E

We received sundry notices from Equitable for both of these wells a month or two ago (sundries dated 2/3/97 and 3/26/97) requesting another one year extension (to expire in 1998). Can you tell me what the latest status is? Are you still rescinding these two permits? Did you not receive the same sundries we did? Did you turn down their request for an extension? Or what?

Your assistance is appreciated! Thank you!!

Don Staley
Utah Division of Oil, Gas and Mining
(801-538-5275)

*Sundry date
2/3/97
requests another
year ✓*

From: Margie Herrmann <mherrmann@ut.blm.gov>
To: NRDOMAIN.NROGM(DSTABLEY)
Date: 5/9/97 9:24am
Subject: RESCIND LETTERS - Reply

Don,

I received your message. Sorry to be slow in replying, but I have been out sick.

In regard to your question about the following well:

Balcron Monument Fed 42-14J 14-9S-16E
Balcron Monument Fed 22-14J 14-9S-16E
Balcron Monument Fed 43-26 26-8S-17E

We had already extended these locations once, and usually do not give them a second extension. After 2 years we prefer to have the Operator submit a new APD for the location.

As for the sundry notices, no I did not see them.

I will be calling Bobbie this morning.

Let me know if you have any more questions. Also please let me know when you received this as I want to be sure it has gone through.

Thank you
Margie

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

5. Lease Designation and Serial No.

U-096547

6. If Indian, Allottee or Tribe Name

n/a

7. If Unit or CA, Agreement Designation
Jonah Unit

8. Well Name and No.

Balcron Monument Fed #22-14J

9. API Well No.

43-013-31489

10. Field and Pool, or Exploratory Area

Monument Butte/GrnRivr

11. County or Parish, State

Duchesne County, UTAH

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Equitable Resources Energy Company

3. Address and Telephone No.

1601 Lewis Avenue; Billings, MT 59102 (406) 259-7860

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE NW Section 14, T9S, R16E 2134' FNL, 2198' FWL

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other renewal of APD
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water


13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Operator requests a one-year extension for approval of the Application for Permit to Drill this well.

APD extended
to 3/1/98
DTS

CONFIDENTIAL

ORIGINAL: Bureau of Land Management (Vernal, UT)
COPY: Utah Division of Oil, Gas and Mining



14. I hereby certify that the foregoing is true and correct

Signed

Bobbie Schuman

Title

Regulatory and
Environmental Specialist

Date February 3, 1997

(This space for Federal or State office use)

Approved by

Conditions of approval, if any:

Title

Date